TRANSCONTINENTAL GAS PIPE LINE COMPANY LLC

NORTHEAST SUPPLY ENHANCEMENT PROJECT

ENVIRONMENTAL REPORT

APPENDIX K. UPLAND DISPOSAL AGREEMENT

NOVEMBER 2026

This page intentionally left blank.

DONJON MARINE Co., LLC
100 CENTRAL AVENUE
HILLSIDE, NEW JERSEY 07205 U.S.A.

October 31, 2025

Sarah Behrends
Transcontinental Gas Pipe Line, LLC
Transmission & Gulf of Mexico Offshore Projects
2800 Post Oak Blvd.
Houston, TX 77056

Re: Dredging, Processing and Placement Upland of Designated NESE Sediment

Dear Ms. Behrends,

Donjon Marine Co., LLC (Donjon) is pleased to provide the following conditional letters of acceptance for the sediment designated for upland disposal/placement. Donjon commits to support the project utilizing its dredging capabilities and directing the designated sediment to Donjon's permitted processing facility located in Port Newark.

Multiple sites have been identified for the final management of this sediment after processing. In addition, Donjon has also provided a significant storage location, Bayshore Recycling, which Donjon has utilized many times as a balancing mechanism to facilitate management of the flow of the material into the respective sites.

Each facility identified has provided conditional letters of acceptance which indicated additional sampling and testing requirements in accordance with each facility permit. Initiating this process as soon as possible will provide a smooth start and performance for the project.

Please contact me with any questions. Donjon looks forward to supporting this project and will continue to seek additional receiving facilities to provide the most cost-effective approach possible.

Sincerely,

Kerri K. Mullins
Director Environmental Operations

PHONE
(908) 964-8812
(908) 353-2600

FACSIMILE
(908) 964-7426
(908) 353-2710

WEBSITE
www.donjon.com

BAYSHORE
Your recycling solution.
Facility: 75 Crows Mill Road, Keasbey, New Jersey 08832
Mailing: 1041 NJ-36, Suite 200, Atlantic Highlands, NJ 07716
Phone: 732-738-6000 • info@bayshorerecycling.com
www.bayshorerecycling.com

October 31, 2025

Ms. Kerri K. Mullins
Director Environmental Operations
Donjon Marine Co., Inc.
100 Central Avenue
Hillside, New Jersey 07205
Via email: kerri.mullins@donjon.com

RE: Williams Pipeline Project – Bayshore Dredged Material Management
Processed Dredged Material Conditional Acceptance

Dear Kerri:

As you know, Bayshore Recycling Corp (Bayshore) has the ability to accept and handle dredge material. The NJDEP previously approved the facility under Waterfront Development Permit/ Water Quality Certificate/ Acceptable Use Determination Application No: 1225-04-0013.1 WFD 120001. Currently, Bayshore is an acceptable site to manage Processed Dredged Material (PDM) from the Williams Pipeline Project in the facility's designated Processed Dredged Material Temporary Storage Area. We understand that the project is anticipated to generate up to 170,000 CY of Non-Residential Processed Dredged Material (PDM), is slated for upland placement at various landfills in Pennsylvania.

The dredged material will be dewatered and processed prior to barge transport to the Bayshore facility. PDM will be mechanically off-loaded by clam shell rigs or other similar equipment, from arriving barges at the existing bulkhead on the waterfront portion of the site. PDM will be off-loaded into trucks for transportation to the Processed Dredged Material Temporary Storage Area. PDM transferred and staged at the temporary dredge storage area will not be further processed, and will be kept segregated at the facility. PDM will be allowed to cure as required in the temporary storage area before loading into trucks for transport and placement at multiple PA landfills which will identified in the project AUD. In order to accommodate the project schedule and the receiving schedule of the various placement sites, PDM can be stored for an extended period of time, but no longer than 90 days from project end. Should the PDM require storage beyond 90 days, the facility will require notification.

All loading activities will take place within the temporary storage area. Trucks loaded for transport to the landfills will be weighed before leaving the Bayshore facility. Weight tickets for each load generated from our certified scales will be provided.

Prior to project acceptance, Bayshore will be provided with the AUD for review. Please let me know if you have any questions or concerns. We look forward to working with you on this project.

Sincerely,

Jennifer Solewski

BAYSHORE RECYCLING
Jennifer Solewski
Vice President,
Business & Technical Development

BETHLEHEM LANDFILL
Safety · Integrity · Service

October 6, 2025
Donjon Marine
100 Central Avenue
Hillside, NJ 07205
Attn: Kerri Mullins

Rebco Contracting Corporation/Green Universe LLC
541 Stuyvesant Avenue
Lyndhurst, NJ 07071

Kerri Mullins,,

We reviewed the information for the Williams Pipeline Project, we would be willing to accept this material if it meets our criteria and is approved the Pennsylvania Department of Environmental Protection (PADEP). The following paraments would need to analyzed:

- **pH**
- **Ignitability**
- **Reactive Sulfide/Cyanide**
- **TCLP RCRA Metals – Arsenic, Barium, Cadmium, Chromium, Lead, Mercury, Selenium, Silver**
- **TCLP Non RCRA Metals – Aluminum, Antimony, Beryllium, Boron, Copper, Iron, Manganese, Molybdenum, Nickel, Tin, Titanium, Thallium, Zinc**
- **Oil & Grease or Petroleum Hydrocarbons**
- **PCB's**
- **TOX**
- **Free Liquids**
- **Total Solids**
- **Total Volatile Solids (cannot use composite sample, grab sample only)**
- **Sample Map/Diagram along with brief description source of contamination and type of facility where spill occurred**

Analytics (1 sample for every 375 tons) MUST BE A PA ACCREDITED LAB:

Sincerely,

Jennifer M. Canone
Special Waste Representative
Waste Connections Inc.
Bethlehem Landfill/BRADS Landfill/Blue Ridge Landfill
Conshohocken Rail/Berkey's Transfer Station
2335 Applebutter Road
Bethlehem, PA 18015
Office: (610) 317-3200 x3
Cell: (484) 705-4809
Fax: (484) 626-0600
Email: Jennifer.Canone@WasteConnections.com

Tunnel Hill Reclamation LLC
8822 Tunnel Hill Road
New Lexington, OH 43764

WIN Waste Innovations of Seneca County LLC
12500 W. County Road 18
Fostoria, OH 44830

www.win-waste.com

Jeff Kopyta
Market Manager

Telephone: (201) 957-5657
Email: jkopyta@win-waste.com

October 30, 2025

Donjon Marine Co., LLC
100 Central Avenue
Hillside, NJ 07205
Attn: Kerri Mullins-Director Environmental Operations

Re: Letter of Acceptance

To Kerri:

Based upon a thorough review of the Haley and Aldrich report on: Northeast Supply Enhancement Project, Sediment Sampling and Analysis Plan, Analytical Data for Upland Placement, the sediment identified for upland placement meets the acceptance criteria for management at the Tunnel Hill Reclamation and Seneca County Landfills. This is a conditional letter of acceptance which will be finalized upon receipt of additional sampling data performed in accordance with the facility permit and Ohio EPA approval.

Should you have any further questions, please do not hesitate to call or email.

Sincerely,

TUNNEL HILL RECLAMATION LLC
WIN WASTE INNOVATIONS OF SENECA COUNTY LLC

Jeff Kopyta
Market Manager

Pioneer Crossing Landfill

COMPLETE SOLID WASTE DISPOSAL SYSTEMS

2650 Audubon Road
Audubon, PA 19403
484-398-6500
800-222-1818

October 29, 2025

Kerri K. Mullins
Director Environmental Operations
Donjon Marine Co., LLC
100 Central Avenue
Hillside, New Jersey 07205

Dear Ms. Mullins:

Based upon a thorough review of the Haley and Aldrich report on: Northeast Supply Enhancement Project, Sediment Sampling and Analysis Plan, Analytical Data for Upland Placement, the sediment identified for upland placement meets the acceptance criteria for management at the Pioneer Crossing Landfill. This is a conditional letter of acceptance which will be finalized upon receipt of additional sampling data performed in accordance with the facility permit and PADEP approval.

Sincerely,

Matthew J. Mascaro

Director of Transportation

cc: Terry Gadd

White Pines
LANDFILL CORPORATION

A modern sanitary landfill.

515 State Route 442, Millville, PA 17846 • 570-458-4602 • FAX 570-458-6290

October 29, 2025

Kerri K. Mullins
Director Environmental Operations
Donjon Marine Co., LLC
100 Central Avenue
Hillside, New Jersey 07205

Dear Ms. Mullins:

Based upon a thorough review of the Haley and Aldrich report on: Northeast Supply Enhancement Project, Sediment Sampling and Analysis Plan, Analytical Data for Upland Placement, the sediment identified for upland placement meets the acceptance criteria for management at the White Pines Landfill. This is a conditional letter of acceptance which will be finalized upon receipt of additional sampling data performed in accordance with the facility permit and PADEP approval.

Sincerely,

Matthew J. Mascaro

Director of Transportation

cc: Terry Gadd

Printed on recycled paper