



**PROPOSED PROJECT SCOPE
LEIDY SOUTH EXPANSION PROJECT**

PIPELINE	LENGTH IN MILES	MILEPOSTS
1) 36" Hensel Replacement (Line 'D')	6.09	L188.51 to L194.00
2) 36" Hilltop Loop (Line 'D')	2.46	L183.55 to L186.01
3) 42" Benton Loop (Line 'D')	3.55	L116.87 to L120.42

FACILITIES/MODIFICATIONS

- Central Penn North
- 4) Station 605 (Wyoming County, PA)
 - Uprate the two (2) existing EMDs from 15,000 HP to 21,000 HP each
 - 5) Grassroots Compressor Station 607 (Luzerne County, PA):
 - Install two (2) Titan 130 units (23,465 nominal HP at ISO conditions each, 46,930 HP Total)
- Central Penn South
- 6) Compressor Station 610 (Columbia County, PA):
 - Install one (1) Titan 250 units (31,871 nominal HP at ISO conditions)
 - Re-wheel and uprate two (2) existing EMDs from 20,000 HP to 21,000 HP
 - Add unit cooling
 - 7) Grassroots Compressor Station 620 (Schuylkill County, PA):
 - Install one (1) Titan 250 units (31,871 nominal HP at ISO conditions)

**FOR DISCUSSION PURPOSES ONLY
SUBJECT TO CHANGE**

**LEIDY SOUTH EXPANSION PROJECT
PROJECT LOCATION MAP**
 TRANSCONTINENTAL GAS PIPE LINE COMPANY, LLC.
 F-FQ-LS-D-01 Rev A OCTOBER 25, 2018

